



## **NOTICE INVITING QUOTATION**

**NO.23 (3)/NIQ / ESD-CANI/CH / BSNL/2022/**

**Dated: 14.07.2022**

The Sub Engineer (E), Bharat Sanchar Nigam Limited, Electrical Sub Division-CANI, I-floor, RK Nagar Telephone Exchange, RK Mutt road, Chennai-28 (Phone: 044-24615880) Invites on behalf of the B.S.N.L. sealed item rate quotations for the following work, from the contractors satisfying the under mentioned eligibility conditions to be submitted **on or before 3.00 PM on 21.07.2022 in the O/o SDE (E), ESD-CANI, Chennai-28.** The same shall be opened at 3:30 **PM** on the same day.

The work is estimated to cost **Rs 15,336/-** This estimate, however, is given merely as a rough guide.

Name of work: SITC of 2Nos. 380 KVA Engine Alternator set with Acoustic Enclosure for TE Bldg. RK Nagar, Chennai (SW: Providing cabling for battery charger and Misc work)

### **ELIGIBILITY CRITERIA**

**The bidders satisfying the following condition:**

- 1.1 BSNL enlisted contractors in Electrical category of respective class as per their tendering limits.

SITC of 2Nos. 380 KVA Engine Alternator set with Acoustic Enclosure for TE Bldg. RK Nagar, Chennai (SW: Providing cabling for battery charger and Misc work)

**SCHEDULE OF QUANTITIES**

Sl. No	Description of Item	Qty	Rate	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)= (3)x(4)
1	Supplying and laying 3X2.5Sqmm Copper conductor armored cable in the following manner i/c end termination, gland etc as reqd				
a	On surface of Wall/Recess	3.0 Mtrs		Mtr	
	Unit rate in words				
b	In trench/panel	24.0 Mtrs		Mtr	
	Unit rate in words				
c	Cutting the floor i/c plastering	3.0 Mtrs		Mtr	
	Unit rate in words				
2	Removing the existing 4Way TPN vertical DB on surface and refixing in the new location on surface of wall etc as reqd	1Job		Job	
	Unit rate in words				
3	Removing and rerouting the existing 4X25Sqmm al UG cable /4X4Sqmm copper on surface/Duct i/c making connection etc as reqd (approx 40Mtrs)	1 Job		Job	
	Unit rate in words				
4	P/F information display board made of acl flex and digital printing of necessary details of E/A set, estimate No, date of commissioning i/c making the content, coordination, transportation, suitable frame work for fixing it on the surface of the wall complete as reqd. (Note: Instructions and information's will be given by Engineer-in-Charge). (Size: 4' x 3')	1Job		Job	-
	Unit rate in words				
	<b>Total (Net Cost to BSNL) (A)</b>				
	<b>Add GST @ 18% (B)</b>				
	<b>Total (A+B)</b>				

Note:

- (i) The evaluation of the quotations will be based on net cost to BSNL
- (ii) Materials supplied shall be got approved before installation
- (iii) Payment and other terms and conditions are as per BSNL EW 6 & 8
- (iv) Agency shall submit quotations along with eligibility credentials as per above.
- (v) Work has to be carried out in short notice. The time of completion of work is 15days.
- (vi) **RATES SHALL BE QUOTED IN NUMBERS AND SAME SHALL BE INDICATED IN WORDS BELOW THE SCHEDULE FOR EACH ITEM.**