*O/o The Sub-Divisional Engineer BSNL Elec. Sub Division VI*Ground Floor, CTX Bldg,
TE Flower Bazaar, NSC Bose Rd, Chennai-01



NIQ.NO: 02/SDE(E)/ESD-VI/CH/22-23 dt:-10/06/2022

## NOTICE INVITING QUOTATIONS

Sealed Quotations are invited from BSNL Enlisted Contractors/ Agencies/ Specialized firms undertaking Package AC unit Works for the following works on <u>14.06.2022</u> for the following work. The quotations will be opened on the same day at 3.30p.m.

Name of work: Shifting and re-Installation of the 4 Nos of PAC units for OFC at 1st floor of TE Flower Bazar LE Bldg, Chennai. [SW: Miscellaneous PAC Works]

**Schedule of Quantities** 

Sl:No	Description of Item	Qty	Unit	Rate	SGST %		CGST %		Rate per unit i/c of GST	Net Amount	Total Amount i/c of GST
					Rate %	Amount	Rate %	Amount			
1	Supplying and laying following sizes of PVC insulated PVC sheathed armoured U/G cable of 1.1KV grade, conforming to relevent IS on the wall/existing trench, existing cable trays i/c interconnections, end termination, gland earthing for extending power supply to PAc units complete etc. as required										
	4 CORE 16 sq.mm Al UG Cable	52	mtr								
2	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required										
	4 X 16 sq.mm Al UG Cable	4	SETS								

## O/o The Sub-Divisional Engineer BSNL Elec. Sub Division VI

Ground Floor, CTX Bldg, TE Flower Bazaar, NSC Bose Rd, Chennai-01



## भारत संचार निगम लिमिटेड

भारत सरकार का उपक्रम)

## **BHARAT SANCHAR NIGAM LIMITED**

(A Govt. of India Enterprise)

3	Replacement of following items with new one i/c removing the faulty and refixing of the new one in the existing Stulz make 7 TR Precision Package AC Unit etc. as required.										
a	3/8" Copper Vibrator Element	1	Job								
b	Expansion Valve	1	Job								
4	Supply and charging RL 32 Compressor Oil for Topup/charging as required	1	Ltr								
5	Wall opening for Copper Refrigerant pipes/ Cable tray i/c making good the damages etc complete as required	1	Job								
				Total Estimated Amount							
				Total Estimated Amount i/c of GST							

- 1. The work shall be executed within 15 days from the date of issue of work order
- 2. No advance payment will be made.
- 3. 100% Payment will be made as per BSNL terms & conditions on satisfactory completion of work and duly certified by BSNL engineer-in-charge.
- 4. The Work shall be guaranteed by the supply agency for one year from the date of installation for the complete System.
- 5. Responsibility of rectifying faults during the guarantee period for all items executed is the responsibility of the agency only at no extra cost.

Contractor SDE[E]