



23(68)/BSNL/ESD VII/CH/2022

Dt 17.09.2022

Notice inviting Quotation

Sealed quotations are invited by the Sub Divisional Engineer (E), BSNL – Electrical Sub Division VII, Chennai for the following items of works from approved firms/ contractors up to 21.09.2022, 15.00 Hrs and the quotations shall be opened on the same day at 15.30 Hrs.

Name of Work: Providing periodical oil servicing and repair maintenance of EA sets at RSUs under DGM (Chengalpet), Chennai (FY 2022-24) (SW:-Attending the fault in the 40 KVA Alternator in TE siruseri.)

Sl No	HSN / SAC Code	Description of item	Qty	Rate	Unit	Amount	CGS T		SGST	IGS T	Total Amount i/c GST
							%	Amount			
1	2	3	4	5	6	7	8	9 = (7 x 8)	10	11 = (7 x 10)	12 = (7 + 9 + 11)
1		Dismantling and shifting of existing 40 KVA EA set alternator assembly from the engine and moving the alternator from engine chassis to outside the EA room and loading the vehicle and taken to work shop for repairing purpose, after repairing the alternator return to TE siruseri, and unloading the alternator on the EA bed , including lifting, transporting charges, ,man power, tools, tripods etc as reqd	1 Job		Job						

O/o Sub Divisional Engineer (E),
 BSNL Electrical Sub Division VII,
 Chrompet , Chennai-600 047
 E-mail: esd8chennai@gmail.com
 Ph: 044-22386551



BHARAT SANCHAR NIGAM LIMITED
 (A Govt. of India Enterprise)
 Electrical wing

2		Rewinding of the existing alternator rectifier transformer arrangement including buyback the old copper etc as reqd	1 Job	Job										
3		Supply and fixing of Moulded type rectifier diode including removing the faulty diode and fixing new diode, testing commissioning etc as reqd	1 Job	Job										
4		Dismantling the 40 KVA EA alternator and removing the main shaft and repairing it in the workshop rectifying all the mechanical damages and varnishing the winding reassembling ,fixing the main shaft including Aligning the alternator with the base and Engine prime mover with specialised tools and skilled manpower etc as reqd	1 Job	Job										
5		Repairing of existing 125 A EA /EB change over switch interlocking arrangement with suitable fabrication tools and manpower etc as reqd	1 Job	Job										
			Total Cost Excluding GST									Total Cost Excluding GST		

Contractor

Energy Saved is Energy Generated

Sub Divisional Engineer (E), ESD VII