

O/o THE EXECUTIVE ENGINEER (E)
BSNL ELECTRICAL Division III
No. 22, Kellys TE Bldg, Kellys
Chennai-600 010
Phone: 26478616, E-mail:
eee3drive@gmail.com



भारत संचार निगम लिमिटेड
(भारत सरकार का उपक्रम)
BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)

SHORT NOTICE INVITING QUOTATION

No.23(NIQ)/EE(E)/ED-III/CH/2023/ 167

Dated: 26/09/2023

NIQ No.:01/EEE/ED-III/BSNL/CH/23-24

Name of Work :Removing, Refixing and Reinstallation of Solar panel for water proof and leak arrest work in view of fire incident at TE Chrompet

Executive Engineer (E), BSNL Electrical Division – III, CHTD invites sealed item rate quotations from eligible contractors for the above work, up to **15.00 Hrs on 03.10.2023**. The quotations will be opened on the same day at **15.30 Hrs on 03.10.2023**.

EXECUTIVE ENGINEER (E),

BSNL, ED - III, Chennai - 10

Copy to:-

1. Agencies/Notice Board/BSNL tender website
2. The SE (E), EC-2, TNEZ, Chennai for kind information please.
3. The SDE(E)/ JTO (E), ED-VII, Chrompet, CHTD for information and necessary action.

EXECUTIVE ENGINEER (E)

Name of Work : Removing, Refixing and Reinstallation of Solar panel for water proof and leak arrest work in view of fire incident at TE Chrompet

S No	Description of item	Qty	Rate	Unit	Amount	GST	Total
1	Disconnecting, removing and coiling the existing DC cabling arrangement in the PVC pipe connected between switch /MCB DB box in each solar panel(23nos Approx.) to solar inverter and keeping the same in the safe place given by Bldg in charge and reuse the same after civil works completed in terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			
2	Disconnecting, Removing the existing water line pipes arrangements on the terrace of bldg for cleaning purpose of solar panels and keeping the same in the safe place given by Bldg in charge and refixing /relaying the same after civil works completed in terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			
3	Disconnecting, Removing the existing solar panel(Aprox 91nos) from existing arrangements i/c removing the fixing structural arrangement on the terrace of bldg and keeping the same in the safe place given by Bldg in charge and reuse the same after civil works completed in terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			
4	Dismantling and Removing the existing civil block for supporting the structural arrangement on the terrace of bldg with specialised man power and tools and plant etc as required(Aprox 69 blocks)	1 job		job			
5	Disconnecting, Removing the existing earthing arrangements on the terrace of bldg for entire system and keeping the same in the safe place given by Bldg in charge and relaying the same after civil works completed in terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			

6	Shifting of the entire dismantled and removed solar power system like Panels, cables, structural arrangements fixing and earthing system materials from terrace to first floor with safe custody and handling with safe manner without any damage to panel with specialised man power and tools and plant etc as required	1 job		job			
7	Providing and marking on the terrace for fixing the civil block/structural arrangements after civil works completed with specialised man power and tools and plant by shifting /utilising the existing removed materials from first floor to terrace etc as required	1 job		job			
8	Refixing/Reinstallation of the existing removed the solar panel(Aprox 91nos) after civil works completed in terrace i/c making the structural arrangement for fixing on the terrace of bldg and shifting and utilising the same from first floor to terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			
9	Relaying the existing removed DC cabling arrangement in the PVC pipe (after civil works completed) between switch /DC DB (MC4) box in each solar panel(23nos Approx) to solar inverter i/c fixing the box in the structure and terminating the cables in each box and shifting the same from first floor to terrace for reinstallation with specialised man power and tools and plant etc as required	1 job		job			
10	Testing and commissioning the entire system with specialised man power and tools and plant after completing all the works involved etc as required	1 job		job			
Total							

Contractor

**Executive Engineer (E)
BSNL, ED-III,Chennai TD**

Terms and conditions:

- Eligibility criteria: Contractors having successfully completed similar works in BSNL /PSU/TNEB or Installers of solar panel in BSNL /PSU/TNEB**

2. **The rates quoted shall be inclusive of all taxes and duties including GST**
3. The quotations shall be invariably sent to the Executive Engineer (E), Electrical Division- III, 2 nd Floor, Kellys, TE Chennai- 600010 , in **sealed cover**, the name of work and due date of opening etc shall be indicated on the envelope, otherwise it will be summarily rejected
4. **Time allowed for Completion : 1 Month**
5. The competent authority/ EE (E) of BSNL will have the right to accept the quotation in part/ whole or reject altogether without assigning any reason
6. The work shall be carried out as per latest norms of TNEB.
7. For the purpose of this agreement, the term 'GST' shall include Central Goods and Service Tax Act, 2017 (CGST), State Goods and Service Tax Act, 2017 (SGST), Integrated Goods and Service Tax Act, 2017 (IGST), Union Territory Goods and Service Tax Act, 2017 (UTGST) and any other taxes levied under the GST related legislation in India, as may be applicable
8. All taxes except CGST, SGST, UTGST and IGST if any, required to be paid on the invoices as specified in clause above shall be borne by the supplier. The agency shall ensure that entire input tax credit on account of GST is fully creditable to BSNL.
9. All invoices towards the work shall invariably be uploaded through GSTN Portal for processing payments by BSNL.
10. Payment will be made through ERP by Central Settlement Cell of BSNL Chennai Telephones, after successful completion of works and measurement.

Contractor

**Executive Engineer (E)
BSNL, ED-III, Chennai-10**