

**SHORT NOTICE INVITING QUOTATION**

O/o Executive Engineer (E),  
BSNL Electrical Division I  
II flr, Kellys TE,  
22, Kellys Road, Chennai -10



**भारत संचार निगम लिमिटेड**  
(भारत सरकार का उपक्रम)

**BHARAT SANCHAR NIGAM LIMITED**  
(A Govt. of India Enterprise)

The Executive Engineer (E), BSNL Electrical Division -I, BSNL Telephone Exchange, Kellys, Chennai-10 on behalf of the Bharat Sanchar Nigam Limited, is hereby inviting sealed item rate quotations for the following works upto 1500 hours on **15.02.2024** from eligible BSNL Enlisted Contractors/ Agencies as laid down in the BSNL eligibility conditions. The quotations will be opened on the same day at 1530 Hrs

<b>Name of Work:-Shifting of Kushkumar Admin building to KK Nagar TE and Electrification work at 4th floor of KK Nagar TE (SW: Dismantling of EI &amp; Fans / EMS at V &amp; VI floor to facilitate IIM)</b>					
SI No	Description of item	Qty	Rate	Unit	Amount
1	Dismantling and removing of following LT panels / Stablisers / Distribution Boards / Ceiling fans / Light fittings (surface & recess type) / Fire detection panel / PAS items at V & VI floors of KK Nagar TE, including disconnecting the cables with glands, wiring in conduits, earthing connections and shifting, cataloging and stacking the same at the locations specified by the Site incharge etc as reqd				
	a) LT panels (floor&wall mounted)-4Nos				
	b) UPS distribution panel				
	c) 3x32.5KVA bypass panel				
	d) 3x32.5KVA AVR				
	e) 30KVA UPS with isolation transformers - 2Nos				
	g) Multiple way Vertical / Horizontal Distribution boards - 15Nos				
	// All the Above consistng of //	1 Job		Job	
2	Dismantling & Removing of EI & Fans, disconnected cables on surface of wall / in the existing MS tray from the following locations including measuring / coiling / tagging and cataloging the cables and shifting the same to the location specified by the Site incharge etc as reqd				
	All conduits and wires at V & VI floors				
	All Fans & fittings at V & VI floors				
	All fire detection cables & accessories				
	Cables from Raising panel to UPS panel - 60 mtrs (Approx)				
	Cables from UPS panel to Distribution LT panel - 110 mtrs				
	Cables from LT panel to Bypass panel - 30 mtrs (Approx)				
	All other distribution cables & wires				
	MS tray - 60mtrs				

// All the Above consisting of //	1 Job		Job	
3	Dismantling & Removing of 1.5TR / 3TR Split / Slim line type AC units at different locations at V & VI floors of KK Nagar TE including measuring / coiling / tagging and cataloging the copper piping, shifting the indoor / outdoor units to the location specified by the Site incharge etc as reqd - 15Nos (apprx)	1 Job		Job
			Total	
			Add GST 18%	
			Gross Amount	