

O/o The Executive Engineer(E),
BSNL Electrical Division-I,
Chennai Telephones
TE Kellys Compund
No.22, Kellys Road,
Kellys,Chennai-10
PH:26448484
email:ee1chennai@gmail.com



No.23(NIT)/EEE/ED-I/CH/2024/

Dt: 13/03/2024

CORRIGENDUM

Name of Work : Providing power supply arrangement for proposed Power plant for NMS and CNTX and shifting of existing power supply arrangement to new location to implement OBOPOAC concept in a single location at TE Gummidipundi.

NIT No. 74/EEE/ED-I/CH/2023-24

Date of opening of Tender : 16.03.2024

The revised schedule is enclosed along with this corrigendum. The rates for above NIT should be quoted in this schedule only. Rates quoted if any in the original NIT will not be considered.

**/sd/
Executive Engineer(E)**

Name of work: Providing power supply arrangement for proposed Power plant for NMS and CNTX and shifting of existing power supply arrangement to new location to implement OBOPOAC concept in a single location at TE Gummidipundi.

Sl. no	Description of Item	Qty & Unit	Rate / Unit Excluding GST	Total Amount Excluding GST	CGST %	CGST Amount in Rs.	SGST %	SGST Amount in Rs.	IGST %	IGST Amount in Rs.	Total Amount including GST
1	Supply of one number 4 core 35 sqmm PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade as reqd	27Mtrs									
2	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on surface of wall as required										
a	4 core 35 Sq.mm	25Mtrs									
3	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size in the existing panel/RCC/ HUME/ METAL pipe as required										
a	4 core 35 Sq.mm	2Mtrs									
4	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required										
a	4 core 35 Sq.mm	2Sets									

Sl. no	Description of Item	Qty & Unit	Rate / Unit Excluding GST	Total Amount Excluding GST	CGST %	CGST Amount in Rs.	SGST %	SGST Amount in Rs.	IGST %	IGST Amount in Rs.	Total Amount including GST
5	Providing & fixing 6SWG dia GI wire on surface or in recess for loop earthing etc. as reqd	50Mtrs									
6	Supplying & fixing of 63A, TPN switch dis-connector fuse unit in sheet steel enclosure with suitable HRC fuses for operation on 415V 50Hz, 3 Phase AC supply including fixing on surface of wall testing & commissioning etc as reqd. (make:-L& T FN 63 or SS make)	1Job									
7	Supplying and fixing of 100A rating 3 Phase & Neutral Al bus bar arrangement in sheet steel enclosure, insulator supports, for termination of power plant AC supply including fixing on surface of wall testing and commissioning etc as reqd.,	1Job									
8	Providing and fixing copper earth bar of size 25x6mm and 500mm length with necessary holes i/c Providing necessary insulator arrangement etc as required.	1Job									
9	Laying of single core multi-strand copper cable on existing pipe/cable tray etc as required										
	a) Upto 50 Sq.mm	40Mtrs									

Sl. no	Description of Item	Qty & Unit	Rate / Unit Excluding GST	Total Amount Excluding GST	CGST %	CGST Amount in Rs.	SGST %	SGST Amount in Rs.	IGST %	IGST Amount in Rs.	Total Amount including GST
10	Supplying and making end termination with copper lug for 35 Sq.mm single core copper cable as required	6Jobs									
II Existing Supply arrangement(shifted to New location)											
1	Dismantling of existing 100A TPN switch disconnecter fuse unit in sheet steel enclosure on surface of wall etc as reqd.,	1Job									
2	Dismantling of existing 4Core 35sq.mm. Al. armoured cable on surface of wall i/c disconnecting end termination etc as reqd., (approx 21mtrs)	1Job									
3	Installation, Testing & Commissioning of existing 100A TPN switch disconnecter fuse unit in sheet steel enclosure with suitable HRC fuses for operation on 415V, 50Hz, 3 Phase AC supply including fixing on surface of wall testing & commissioning etc as reqd.	1Job									
4	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on surface of wall as required										
a	4 core 35 Sq.mm	45Mtrs									

Sl. no	Description of Item	Qty & Unit	Rate / Unit Excluding GST	Total Amount Excluding GST	CGST %	CGST Amount in Rs.	SGST %	SGST Amount in Rs.	IGST %	IGST Amount in Rs.	Total Amount including GST
5	Making end termination with existing brass compression gland & aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required										
a	4 core 35 Sq.mm	2 Sets									
6	Laying of existing 6SWG dia GI wire on surface or in recess for loop earthing etc. as reqd	40Mtrs									
7	Laying of single core multi-strand copper cable on existing pipe/cable tray etc as required										
a	Upto 50 Sq.mm	40Mtrs									
8	Supplying and making end termination with copper lug for 35 Sq.mm single core copper cable as required	4 Jobs									
9	Dismantling the existing copper earth bar of size 25x6mm and 500mm length arrangement and re fixing the same to the other location etc as required.	1 Job									
Total Net cost (excl. GST) Rs.					Total cost (Incl. GST) Rs.						

Total Net cost (excl. GST) in words Rupees

CONTRACTOR

EE(E), ED-1

IMPORTANT NOTES:-

1	The firm shall be responsible to ensure that GST shown in the above columns is correct & Input Tax Credit for the amount shown above is admissible as per GST Act as amended up to date”.
2	Invoice /Bill should be pre-printed as per the GST format.
3	The evaluation and comparison of responsive bids shall be done on the basis of Net cost to BSNL on the prices offered inclusive of packing, forwarding, freight and insurance charges etc., but excluding GST
4	The rates for all items of work shall, unless clearly specified otherwise, include cost of all labour, materials and other inputs involved in the execution of the terms as specified in the scope of work.
5	No advance payments can be made. Stipulations like levy of interest if payment is not made in a specified time are also not acceptable and the payment is governed by the normal BSNL practice.

